

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-081-00178-0000

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Hölmstrom of Kan.-Neb. Nat Gas Co. has this  
date requested permission to plug the following described well:

Mr. Hölmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas-Nebraska Natural Gas Co.

Complete Address: Lakin, Kansas

Lease Name: June Well No. 1

Location: NW NW SE Sec. 8 Twp. 28 Rge. 32 (EX) (W)

County Haskell Total Depth 2772' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Hölmstrom was instructed to plug the well as follows:

10 3/4" to 616' circulated w/ cement. 7" to 2764' cemented

Top Perf. 2708' Plug bottom w/ 25 sacks cement.

Top of cement 2588' Mud 2588' to 630'

Spotted 50 sacks cement 630' to 530' Mud 530' to 40'

Plug, Halls & 20 sacks cement 40' to 0 Company Pump

Very truly yours,

Edgar J. Eves  
Conservation Division Agent