



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-081-00198-0000

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bentley of J.M. Huber has this date requested permission to plug the following described well:

Mr. Bentley guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 911, Amarillo, Texas 79105

Lease Name: Poor Farm Well No. 1

Location: App Center Sec. 32 Twp. 28 Rge. 32 (E) (W)

County: Haskell Total Depth 2733' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Bentley was instructed to plug the well as follows:

8 5/8" to 600' circulated w/ cement. 5 1/2" to 2650' cemented.

Hole in 5 1/2" casing and well filled w/ sand to 1151'

Mud 1151' to 650' Spotted 50 sacks cement 650' to 500'.

Mud 500' to 35' Plug, Halls & 10 sacks cement 35' to 0'.

Very truly yours,

Conservation Division Agent