



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-20005-0000

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 4 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ipson of Ashland Oil has this

date requested permission to plug the following described well:

Mr. Ipson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 127, Satanta, Kansas

Lease Name: F. Roy Well No. 5-A

Location: C SE Sec. 4 Twp. 28 Rge. 33 (E)(W)

County: Haskell Total Depth 2859' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Ipson was instructed to plug the well as follows:

8 5/8" to 770' circulated w/ cement. 5 1/2" to 2859' cemented.

Top peffs. 2663' Plug bottom w/ 20 sacks cement

Top of cement 2350' Mud 2350' to 700'

Spot 40 sacks cement 700' to 600' Mud 600' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar F. Evers
 Conservation Division Agent