



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-081-00268-6000

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ipson of Ashland Oil has this

date requested permission to plug the following described well:

Mr. Ipson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 127, Satanta, Kansas

Lease Name: F. Roy Well No. 5

Location: App. Center Sec. 4 Twp. 28 Rge. 33 (E) (W)

County: Haskell Total Depth 2767' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Ipson was instructed to plug the well as follows:

10 3/4" to 675' circulated w/ cement. 7" to 2729' cemented.

Top perforations 2647' Well sanded up to 2000'

Mud 2000' to 800' Spot 25 sacks cement 800' to 675'

Mud 675' to 630' Spot 45 sacks cement 630' to 470'

Mud 470' to 40'. Plug, Hulls & 15 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
 Conservation Division Agent