



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-081-30066-0000

RECEIVED
 STATE CORPORATION COMMISSION

DEC - 9 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Duncan of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: Cities-Service Oil Co.

Complete Address: Box 6 Liberal, Kansas

Lease Name: Piland Well No. # A-1

Location: SW SE Sec. 5 Twp. 28 Rge. 34 (E)(W)

County Haskell Total Depth 5550' Oil Well X

Gas Well Input Well SWD Well D & AX Lost Hole

Mr. Duncan was instructed to plug the well as follows:

8 5/8" - 1930' Circulated w/cement. 4 1/2" - 5448' Cemented. Top perforations - 5318'
Plug bottom w/20 Sax. cement top cement at 5100'. Mud 5100' to 700'
Spotted 35 Sax. cement 700' to 550'. Mud 550' to 45'
Plug, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent