

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-30099-0000

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1967

CONSERVATION DIVISION
WICHITA, KANSAS

1-23-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ryan of Pan American Petro. has this
date requested permission to plug the following described well:

Mr. Ryan guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Company

Complete Address: Box 432, Liberal, Kansas

Lease Name: A.R. Berger Well No. 1

Location: SW NW NW Sec. 6 Twp. 28 Rge. 34 (X) (W)

County Haskell Total Depth 4250' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ryan was instructed to plug the well as follows:

8 5/8" to 727' circulated w/ cement. 4 1/2" to 4249' cemented.

Top perforations 4147' Plug, bottom w/115 sacks cement

Top of cement 4000' Mud 4000' to 1400'

Spotted 20 sacks cement 1400' to 1340' Mud 1340' to 640'

Spotted 35 sacks cement 640' to 540' Mud 540' to 45'

Plug, Halls & 10 sacks cement 45' to 0'.

Very truly yours,

Edmund J. Eves
Conservation Division Agent