



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-10050-0001

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Malonee of Malonee-Coppinger Operations Inc.

date requested permission to plug the following described well:

Mr. Malonee guarantees payment of the plugging fee.

Operator's full Name: Malonee-Coppinger Operations Inc.

Complete Address: 1207 Union Nat. Bldg. Wichita, Kansas

Lease Name: Eubank Well No. # 1

Location: C SE SE Sec. 7 Twp. 28 Rge. 34 (E) (W)

County Haskell Total Depth 5403' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Malonee was instructed to plug the well as follows:

8 5/8"-1909' Circulated w/cement. 4 1/2"-5722' Cemented. Perforations-5399 1/2".

Plug bottome w/20 Sax.cement top cement 5220'. Mud 5220' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 Sax.cement 45' to 0

Very truly yours,

Conservation Division Agent