

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-081-10064-0000

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Graham-Michaelis Drilling has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Company

Complete Address: Box 1294, Liberal, Kansas

Lease Name: Eubank Well No. 3-28

Location: App C W/2 NE Sec. 28 Twp. 28 Rge. 34 (E)(W)

County Haskell Total Depth 5605' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 782' circulated w/ cement. 4 1/2" to 5604' cemented

Top perforations 5472' Plug Bottom w/ 20 sacks cement

Top of cement 5300' Mud 5300' to 700'

Spotted 40 sacks cement 700' to 575' Mud 575' to 35'

Plug, Hulls & 10 sacks cement 35' to 0'

Very truly yours,

Edgar A. Eves
Conservation Division Agent