

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-20,603-000

LEASE NAME Droll "A"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 32 TWP. 28 RGE. 32 (E or W)

COUNTY Haskell

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS. 67905

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 2/26/90

Plugging Commenced 2/26/90

Plugging Completed 2/27/90

The plugging proposal was approved on 2/26/90 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Yes

Producing Formation NA Depth to Top -- Bottom -- T.D. 5640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf	1785	8 5/8	1785	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set 80 sxs cmt plg. @ 3000, 50 sxs, cmt plg @ 1798, 40 sxs cmt plg. @ 750, 10 sxs cmt plg @ 40, 15 sxs cmt in rat hole. Heavy DM pmpd between each plg, cmt 60/40 Poz. 6% gel.
Restore Location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gabbert-Jones, Inc. License No. 5842

Address 333 E. English Suite 215, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.


Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Engineering Tech
(Address) P.O. Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 90

C Cheryl Steers
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1990
CONSERVATION DIVISION
Wichita, Kansas

3-29-1990