

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Form CP-4
15-081-00198-0000

WELL PLUGGING RECORD

Haskell

County, Sec. 32, Twp. 28S, Rge. 32W (E) (W) 32

Location as "NE/CNW/SW" or footage from lines 150' S&W of Center Sec. 32

Lease Owner J. M. Huber Corporation

Lease Name Poor Farm Well No. 1

Office Address P. O. Box 911, Amarillo, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed March 29, 1953

Application for plugging filed December 15, 1969

Application for plugging approved December 18, 1969


Plugging commenced December 17, 1969

Plugging completed December 17, 1969

Reason for abandonment of well or producing formation Unprofitable

If a producing well is abandoned, date of last production July 1969

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves

Producing formation Hugoton Depth to top 2660 Bottom 2733 Total Depth of Well 2733 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hugoton	Lime	2660	2733	5-1/2	2660	1124'

RECEIVED
STATE CORPORATION COMMISSION
DEC 31 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand fillup to 1117'. Received 1124' of 5-1/2 14# J-55 casing. Spotted 50 sacks cement 650'-550', mud laden fluid 550'-35', 10 sacks cement 35'-5'. Cut off surface casing & capped.

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Lease & Well Service
Address 1700 S. Main, Borger, Texas 79007

STATE OF Texas, COUNTY OF Potter, ss. Bob Conley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bob Conley
P.O. Box 911, Amarillo, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1969

My commission expires June 11, 1971

Sharon E. Dawell
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1970
CONSERVATION DIVISION
Wichita, Kansas

Poor Farm #1
Section 32-28S-32W
Haskell County, Kansas

15-081-00198.0000

Driller's Log

<u>Depth</u>	<u>Formation</u>
0'-110'	Clay & Surface Rock
110'-350'	Sand
350'-450'	Shale & Sand
450'-1845'	Red Bed & Shale
1845'-1870'	Anhydrite
1870'-2270'	Shale
2270'-2660'	Lime & Shale
2660'-2733'	Lime
T.D. -2733'	

Certificate:

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Bob Corley
Bob Corley

Title: District Production Clerk

Subscribed and sworn to before me, a Notary Public,
this 3rd day of February 1970.

Sharon E. Dowell
Notary Public

*My Commission Expires
June 1, 1971*