

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-081-00205-0000

API NUMBER N/A - Drilled before 1967

LEASE NAME Anschutz "A"

WELL NUMBER 1

SPOT LOCATION 1326' FNL
1329' FSL

SEC. 2 TWP. 28 RGE. 33 (E) OR (W)

COUNTY Haskell

DATE WELL COMPLETED 12/22/54

PLUGGING COMMENCED 2/21/84

PLUGGING COMPLETED 2/24/84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444, Denver, CO 80217

PHONE # (303) 298-2696 OPERATORS LICENSE NO. 5208

CHARACTER OF WELL gas
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dist. #1, 302 W. McArtor, Dodge City, KS

IS ACC-I FILED? WILL BE Forwarded IF NOT, IS WELL LOG ATTACHED? -

PRODUCING FORMATION Hugoton DEPTH TO TOP 2680 BOTTOM 2754 T.D. 2800

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Upper Krider	gas	2680	2690	9 5/8"	548	0
Winfield	gas	2710	2754	5 1/2"	2772	1108'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pumped 2 sx of hulls - 35 sx cement - 5 sx gel & 25 sx cement to 1618'. Shot off at 1407' couldn't pull. Shut off at 1108', pulled 30. Pumped 11 sx gel and 70 sx cement to 900-1000'. Pulled casing to 600', pumped 50 sx cement 600' to 475', pulled all of casing. Put bridge and 10 sx of cement 40' to 0'. Cut off 9 5/8" - 5' below ground level. Weld on plate.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Midwest Casing & Pulling LICENSE No. 6497
ADDRESS P. O. Box "F", Sublette, Kansas 67877

STATE OF Kansas COUNTY OF Stevens, SS.

C. J. Park (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) C. J. Park C. J. Park
Producing Accounting Supervisor
(ADDRESS) P. O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF April, 1984

Judith A. Olsen
NOTARY PUBLIC

MY COMMISSION EXPIRES: 11-28-84

RECEIVED
STATE CORPORATION COMMISSION FORM CP-4
APR 18 1984 REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas