


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Haskell County, Sec. 5 Twp. 28 Rge. 33 (E) (W)  
Location as "NE/CNW%SW%" or footage from lines 150' S.E. Center of Section  
Lease Owner J. M. Huber Corporation  
Lease Name Currey #1 Well No. \_\_\_\_\_  
Office Address Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Feb. 3, 1953 19\_\_\_\_  
Application for plugging filed Feb. 4, 1953 19\_\_\_\_  
Application for plugging approved Feb. 4, 1953 19\_\_\_\_  
Plugging commenced Feb. 5, 1953 19\_\_\_\_  
Plugging completed Feb. 5, 1953 19\_\_\_\_  
Reason for abandonment of well or producing formation  
Dry Hole  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2781' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				618'	8 5/8"	None
				5-9/16"	2759'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled w/mud to 2735'. Bridged w/rock to 2730' and dumped 5 sacks of cement.  
Loaded hole w/mud to 350'; bridged w/rock and dumped 20 sacks of cement.  
Filled w/mud to 35'; bridged w/rock and filled w/10 sacks of cement to top of cellar.

FILED

2-23-53

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Plugged w/Rotary Tools - (Prime Drilling Co.)  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.  
I, W. W. Henson (employee of owner) or (owner) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) W. W. Henson

(Address) \_\_\_\_\_  
SUBSCRIBED AND SWORN TO before me this 18th day of February, 1953  
My commission expires Sept. 10, 1955  
J. L. Keyler  
Notary Public.

**PLUGGING**  
FILE SEC 5 T 28 R 332  
BOOK 27 LINE 37

5-681-00260-0000

J. M. Huber & L. Currey  
Section 5 - TWP 28S Range 33West  
Haskell County, Kansas

DRILLERS LOG

<u>Formation</u>	<u>Depth</u>
Sand	0-305
Sand and Shale	305 - 325
Shale and Shells	325 - 560
Red bed and Shells	560 - 650
Sand	650 - 725
Gray Shale	725 - 925
Red bed, shale & shells	925 - 1325
Anhydrite	1325 - 1395
Shale & Shells	1395 - 2210
Lime & shale	2210 - 2759
Lime	2759 - 2793
T. D.	2793

**PLUGGING**  
 FILE SEC. 5-T-28-R-334  
 BOOK PAGE 27 LINE 37

CERTIFICATE

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

R. E. McDaniel  
R. E. McDaniel

Title: Petroleum Emgr.

Subscribed and sworn to before me, a Notary public, this 21 day of

April 1953

RECEIVED  
REGISTRATION COMMISSION

REGISTRATION DIVISION  
Kansas

D. L. Kyle