

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-081-20400-0000

LEASE NAME Ochs

WELL NUMBER 1-25

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 28S RGE. 33W (E) or (W)

COUNTY Haskell

LEASE OPERATOR Global Natural Resources Corporation

ADDRESS P.O. Box 4682
Houston, Texas 77210

PHONE# (713) 880-5464 OPERATORS LICENSE NO. 4328

Date Well Completed

Character of Well Oil

Plugging Commenced 2-5-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-11-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is AGO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1662'	none
				5-1/2"	5600'	2479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 5250' and 5 sacks cement. Shot pipe @2700', 2600', 2500', 2479', pulled a total of 59 joints of 5-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 20 gel, 1 hull, 150 cement, 60/40 pos, 6% gel.
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 23rd. day of Februray, 19 87

James Hoover
 Notary Public
 STATE CORPORATION COMMISSION

My Commission Expires:



2-25-1987
 FEB 25 1987 Form CP-4
 Revised 07-86
 CONSERVATION DIVISION
 Wichita, Kansas

FINAL LOG

Schlumberger

CEMENT BOND/VARIABLE DENSITY LOG

CSU

COMPANY: GLOBAL NATURAL RESOURCES

WELL: DCHS #1-25

FIELD: WILDCAT

COUNTY: HASKELL

STATE: KANSAS

NATION: USA

LOCATION: NE/SE

CONFIDENTIAL

SEC: 25

TWP: 28S

RGE: 33W

PERMANENT DATUM: GROUND LEVEL ELEVATIONS-
 ELEV. OF PERM. DATUM: 2939.0 F KB: 2951.0 F
 LOG MEASURED FROM: KB DF: 2949.0 F
 12.0 F ABOVE PERM. DATUM GL: 2939.0 F
 DRLG. MEASURED FROM: KB

DATE: 10 JAN 86
 RUN NO: 1

DEPTH-DRILLER: 5513.0 F
 DEPTH-LOGGER: 5505.0 F
 BTM. LOG INTERVAL: 5493.0 F
 TOP LOG INTERVAL: 2545.0 F

CASING-DRILLER: 1663.0 F 5600.0 F 0.0 F
 CASING-LOGGER: 1662.0 F 0.0 F 0.0 F
 CASING: 8 5/8 5 1/2
 WEIGHT: 24.0000 LB/F 17.0000 LB/F 0.0 LB/
 BIT SIZE: 12 1/4 7 7/8
 DEPTH: 1662.0 F 0.0 F 0.0 F