


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Haskell County. Sec. 5 Twp. 28S Rge. KK 34 (W)
Location as "NE/CNW/SW" or footage from lines G SW SE
Lease Owner Cities Service Oil Company
Lease Name Piland "A" Well No. 1
Office Address Box 6 - Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 19 19 65
Application for plugging filed December 2 19 65
Application for plugging approved December 3 19 65
Plugging commenced December 4 19 65
Plugging completed December 8 19 65
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 5550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow S-3	Salt Water	5398	5408	8 5/8"	1930	0
Morrow Lime	Salt Water	5318	5330	4 1/2"	5438	2693

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1966

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot plug 20 sacks 4857-5107'
Gel from 700-4857'
Spot plug thru casing 30 sacks 600-700'
Gel from 45-600'
Spot plug thru casing 15 sacks 0-45'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gayle Toland
Address Woodward, Oklahoma

STATE OF Kansas, COUNTY OF Seward, ss.
C. A. Nenney (employee of owner) or ~~(owner or operator)~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Nenney G. A. Nenney

Box 6 - Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 65

My commission expires 11-5-66

Calvin Lindsey
Calvin Lindsey Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 3 1965

CONSERVATION DIVISION
Wichita, Kansas

15-081-30066-0000

ROTARY DRILLING LOG

OWNER: Cities Service Oil Company CASING: Set 8 5/8" 24# casing at
CONTRACTOR: Rine Drilling Co. 1930', cemented w/600 sx
LEASE: Piland "A" #1 cement
LOCATION: C SW SE Sec. 5-28S-34W
Haskell County, Kansas

0 - 865	Sand, gravel & red bed
865 - 1840	Sand, red bed & gyp
1840 - 1930	Red bed & gyp
1930 - 1935	Anhydrite
1935 - 2850	Lime
2850 - 2990	Lime & shale
2990 - 3334	Lime
3334 - 3635	Lime & shale
3635 - 3929	Shale
3929 - 4065	Lime, shale & chalk
4065 - 4386	Lime & shale
4386 - 4790	Lime
4790 - 5024	Lime & shale
5024 - 5177	Lime
5177 - 5293	Lime & shale
5293 - 5550	Lime
5550	Rotary Total Depth

D & A

We certify that the above log is true and correct to the best of our knowledge and belief.

CITIES SERVICE OIL COMPANY

BY C. A. Nenney
C. A. Nenney
District Engineer