

15-081-30001-00-01

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

County. Sec. 8 Twp. 28 SRge. 34 ~~WEN~~ (W)

Location as "NE/CNW%SW%" or footage from lines C of SE/4 of SW/4

Lease Owner W. J. Coppinger

Lease Name Dubois Well No. 2

Office Address 1207 Union National Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Jan. 17, 1965 19

Application for plugging filed Jan. 14, 1965 19

Application for plugging approved Jan. 14, 1965 19


Plugging commenced Jan. 14, 1965 19

Plugging completed Jan. 17, 1965 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 5705 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	175	400	8/5/8	910	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 185 Sacks plug from 2500 to 3000' spotted by Haliburton pump down pipe.

Set 25 sack plug @700' to 675' spotted by Haliburton pumped down drill Pipe.

Set 15 sacks put @40 to 10' pump into top of hole by Halliburton.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1965

CONSERVATION DIVISION
Wichita, Kansas

1-20-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mahoney Drilling Co. Inc.

Address Box 1257, Liberal, Kansas

STATE OF KANSAS, COUNTY OF Seward, ss.

Dale Dwight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Dwight

P.O. Box 1257 Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of January, 19 65

George W. Carnahan Jr.
Notary Public.

My commission expires January 24, 1968

Dubois # 2
Section 8-28S34W
Haskell County, Kansas

Started 12/29/64
Set 8 5/8" Csg. 909' 500 Sx.
Cement Circulated
Plug 1/17/65

15-081-30001-0000

Sand & Clay	0-510
Gyp & Anhydrite	510-860
Red Bed	860-910
Red Bed & Sand	910-1710
Sand & Shale	1710-2110
Sahle & Anhydriet	2110-2330
Shale & Lime	2330-2515
Lime & Shale	2515-2780
Lime	2780-2880
Lime & Shale	2880-4035
Lime	4035-5200
Lime & Shale	5200-5321
Lime	5321-5390
Lime & Sand	5390-5410
Lime	5410-5705
T.D.	5705

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1965
CONSERVATION DIVISION
Wichita, Kansas

This is a true and exact copy of the formatinn, taken from
The Daily Drilling Reports.

MAHONEY DRILLING COMPANY INC.

J. W. Mahoney

STATE OF KANSAS
COUNTY OF SEWARD

SWORN TO BEFORE ME THIS 18 DAY OF JANUARY, 1965

George W. Carnahan Jr.
NOTARY PUBLIC

MY COMMISSION EXPIRES JANUARY 24, 1968