

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078/ED
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

15-081-10065-00-07
API NUMBER Spud 1/23/61

LEASE NAME Eubank

WELL NUMBER 7 SWD EDR

3300 Ft. from Sⁿ Section Line

660 Ft. from E Section Line

SEC. 28 TWP. 28 S. R. 34 (E) or (W)

COUNTY Haskell

Date Well Completed 1961

Plugging Commenced 8/1/02

Plugging Completed 8/8/02

SEP 12 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA
9-12-2002

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS 1579 E. 21st Tulsa, OK 74114

PHONE(S) (918) 742-5531 OPERATORS LICENSE NO. 5293

Character of Well SWD EDR

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/2/02 (date)

by Steve Durant - verbal approval (KCC District Agent's Name).

Is ACD-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5494' Bottom 5514' T.O. 5560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	859	8 5/8	859'	NONE
		0	5560	4 1/2	5560'	NONE
		0	5516	2 7/8	5516'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set 2 7/8" Baker Model B plug on WL @ 5548' w/2 sks cmt. Perforate 2 7/8" & 4 1/2" on casings at 900'. Pump 175 sxs 40/60 from 900' to surface. Circulated 33 sxs cmt to pit. Place cement from 900' to surface inside 2 7/8" and from 900' to surface in 4 1/2" 8 5/8" annulus

Name of Plugging Contractor Halliburton License No. 5287

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.


STATE OF Oklahoma COUNTY OF Tulsa, ss.

David Cook - Prod. Supt. (Employee of Operator) or (Operator) c
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed and
the same are true and correct, so help me God.

(Signature) David L Cook

(Address) 1579 E. 21st, Tulsa, OK 74114

SUBSCRIBED AND SWORN TO before me this 10th day of September, 2002



Commission Expires: 4/9/05
Amy Warren
Notary Public

CR