

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-081-10072-0000
WELL PLUGGING RECORD

NORTH

			#

Locate well correctly on above
Section Plat

Haskell County. Sec. 28 Twp. 28 Rge. 34 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. 0 SE SE
Lease Owner Helmerich & Payne Inc.
Lease Name Eubank Well No. 6
Office Address 310 1/2 N. Main Garden City, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ 19____
Application for plugging filed Sept. 6, 1961
Application for plugging approved Sept. 6, 1961
Plugging commenced Sept. 6, 1961
Plugging completed Sept. 8, 1961
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5625' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8 4 1/2	790' 5526'	none 1969'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 4750' to 4700'. Mixed and dumped 4 sx. cement from 4700' to 4668'. Pulled casing. Mudded hole from 4668' to 525'. Set 10' rock bridge from 525' to 515'. Mixed and dumped 20 sx. cement from 515' to 455'. Mudded hole from 455' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. cement from 30' to base cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1961

CONSERVATION DIVISION
Wichita, Kansas

9-19-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Finney, ss.
T. E. Mort (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. E. Mort
Helmerich & Payne, Inc., Box 255, Garden City, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 61

My commission expires July 1, 1964

Robert N. Boyd
Notary Public.

15-081-10072-0000

Eubank No. 6
Helmerich & Payne, Inc.
Section 28-28S-34W
Haskell County, Kansas

CASING RECORD:

24 Jts. 8-5/8" 24# Csg. w/350 sx. Pozmix; 2% CC and
100 sx. Common; 2% CC. Set at 792'
100 Jts. 4-1/2" @ 5526' w/300 sx. Reg.

COMMENCED: 6-10-61
COMPLETED: 6-26-61

	<u>FROM</u>	<u>TO</u>
Surface	0	792
Redbed & Shale	792	1450
Sand & Shale	1450	2835
Shale	2835	3010
Lime & Shale	3010	3728
Chalk & Lime	3728	3991
Lime & Shale	3991	4880
Lime	4880	5005
Lime & Shale	5005	5075
Lime	5075	5115
Lime & Shale	5115	5507
Lime	5507	5625
<u>TOTAL DEPTH</u>		<u>5625</u>

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1961
CONSERVATION DIVISION
Wichita, Kansas

STATE OF OKLAHOMA)
) SS
County of Tulsa)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Eubank No. 6 well, located in Section 28-28S-34W, Haskell County, Kansas.

HELMERICH & PAYNE, INC.

[Signature]
Vice President

Subscribed and sworn to before me a Notary Public this 10th day of July, 1961.

[Signature]
Notary Public

My commission expires March 30, 1964.