


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-173-00406-0000

NORTH



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 4 Twp. 26S Rge. 1 (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner Halliburton Oil Producing Company & Twin Drilling, Inc.  
Lease Name Burge Well No. 1  
Office Address 2915 Glassen Blvd., Oklahoma City 6, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-23 19 59  
Application for plugging filed 11-30 19 59  
Application for plugging approved 11-23 19 59  
Plugging commenced 11-23 19 59  
Plugging completed 11-23 19 59  
Reason for abandonment of well or producing formation  
Dry Hole  
If a producing well is abandoned, date of last production None 19     
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee N. Guthrie, Leon, Kansas

Producing formation    Depth to top    Bottom    Total Depth of Well 3895 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	181.25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet for each plug set.

Set solid plug at 180'. Cemented with 15 sacks cement.

Fill hole up to 30' of base of cellar and cap with

10 sacks cement. 2 Sacks cement in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1959

CONSERVATION DIVISION  
Wichita, Kas

12-2-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Twin Drilling, Inc.  
Address 1005 Central Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Almeda Day

(employee of owner) ~~as owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Twin Drilling, Inc.

Almeda Day  
(Address) Secretary

SUBSCRIBED AND SWORN TO before me this 1 day of December, 19 59

James S. Hick  
Notary Public.

My commission expires September 29, 1960



R

15-173-00406-0000

WELL LOG

Well: Burge #1 Location: SE/4 SE/4 NE/4  
Operator: Halliburton Oil Producing Co. Section 4-26S-1W  
2915 Classen Blvd. Sedgwick County, Kansas  
Oklahoma City 6, Oklahoma  
Commenced: 11-9-59  
Completed: 11-23-59  
Contractor: Twin Drilling, Inc.  
1005 Central Building  
Wichita, Kansas  
Casing: 8 5/8" 181.25' Surface W/175 Sacks

Sand & Gravel	160
Shale	285
Shale & Shells	370
Lime & Shale-Broken	700
Lime & Shale	2015
Lime	2098
Lime & Shale	2490
Lime W/Shale Streaks	2620
Lime & Shale	2760
Lime	2920
Lime & Shale	3005
Lime	3071
Shale & Lime	3315
Lime	3495
Cherty Lime	3530
Lime & Chert	3614
Lime	3665
Lime & Shale	3750
Shale	3770
Shale & Sand	3860
Lime	3895

T.D. 3895'

STATE OF KANSAS  
SEAL OF THE STATE COMMISSION

DEC 2 1959

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
) ss.

COUNTY OF SEDGWICK )

The undersigned, TWIN DRILLING, INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

TWIN DRILLING, INC.

By: Alvin A. Day

Subscribed and sworn to before me  
this 1st day of December, 1959.

James A. Nick  
Notary Public

My commission expires  
September 29, 1960.