

STATE OF KANSAS
STATE CORPORATION COMMISS:
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-151-80910-00-01

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 4-14-61 completion (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Citation Oil & Gas Corp. KCC LICENSE # 03553
(owner/company name) (operator's)

ADDRESS 8223 Willow Place South Ste 250 CITY Houston

STATE Texas ZIP CODE 77070 CONTACT PHONE # (713) 469-9664

LEASE Moore WELL# 1 SEC. 28 T. 29 R. 13 (East/West)

C - SW - SE - SPOT LOCATION/QQQQ COUNTY Pratt

300' FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

2310' FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check Ode: OIL WELL x GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 953 CEMENTED WITH 475 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4710' CEMENTED WITH 135 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4411-4388' CIBP @ 4450' w/6' cmt on top.

ELEVATION 1884' GR T.D. 4715' PBD 4474'-88' cmt plug 4505'-4530'
(G.L./K.B.) ANHYDRITE DEPTH
(Stone Corral Formation)

CONDITION OF WELL: GOOD x POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU PU. POOH. LD rods & pmp. POOH & LD tbg. Dig out WH.
Hook up to 4 1/2" csg & pmp 260 sx 60/40 POZ cmt w/8% gel down csg. Hook up to 8 5/8" csg & pmp 100 sx 60/40 POZ cmt w/8% gel down sfc csg w/hulls. Cut off WH & weld plate on.

RECEIVED

(If additional page is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? JUN 09 1995

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Citation Oil & Gas Corp. PHONE# (405) 681-9400

ADDRESS 4848 SW 36th Street City/State Oklahoma City, OK 73179

PLUGGING CONTRACTOR Halliburton Services KCC LICENSE # 5287

ADDRESS 1108 East 7th Street Hays, KS 67601 PHONE # (913) 625-3431

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6-19-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-8-95 AUTHORIZED OPERATOR/AGENT: Sharon Woral
(signature)



Kansas Corporation Commission

Joan Finney, Governor Jim Robinson, Chairman F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 10, 1994

Citation Oil & Gas Corporation
8223 Willow Place South Ste 250
Houston TX 77070

Moore #1
API 15-N/A
300 FSL 2310 FEL
Sec. 28-29S-13W
Pratt County

Dear Don Jennings,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 1995

CONSERVATION DIVISION
WICHITA, KS

Sincerely,
David P. Williams

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

William R. Bryson, Director Conservation Division

KCC, Conservation Division, 200 Colorado Derby Bldg., 202 W. 1st St., Wichita, Kansas 67202-1286 (316) 263-3238