

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

15-081-00203-0000

FILE NO. 108-13

LOCATION Approx Center

SEC. 1 TWP. 28S RGE. 33W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have this date completed supervision of plugging of:

Well No. 1 Lease Boyd

Operator National Associated Petroleum Co. Address 502 Ritz Bldg., Tulsa, Okla.

Field Hugoton County Haskell

Total Depth 2788 Feet.

Plugging Contractor Halliburton Oil Well Cementing Co.

Plugging Contractor's License No. \_\_\_\_\_

Address Garden City, Kansas

(Describe briefly the manner in which the well was plugged)

8-5/8" 603 feet circulated with cement

2765 feet of 5-1/2" circulated with cement.

Spotted twenty-five sacks of cement on bottom. Plugged back

to 2520 feet. Loaded hole with heavy mud to 200 feet. Set

bridge at 200 feet. Plugged back to surface with twenty-five sacks cement.

Cut-off surface 4' below surface and welded steel cap on casing.

District Conservation Agent

**PLUGGING**  
FILE SEC 1 T 28 R 33  
PAGE 108 OF 13

DATE April 20, 1955