



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

15-081-00208-0006

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 127, Satanta, Kansas 67870

Lease Name F. Roy Well No. 5

Location App. Center Sec. 4 Twp. 28 Rge. 33 (E) (W)

County Haskell Total Depth 2767'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 29 Month 1 Year 1969

The Above well was plugged as follows:

10 3/4" to 675' circulated w/ cement. 7" to 2729' cemented.

Top perforations 2647' Well Sanded up to 2000'

Mud 2000' to 800' Spotted 25 sacks cement 800' to 675'

Mud 675' to 630' Spotted 45 sacks cement 630' to 470'

Mud 470' to 400' Plug, Hulls & 15 sacks cement 40' to 0'

Company Pump Pulled 650' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Green
Well Plugging Supervisor

DATE 2/3/69
INV. NO. 9269-11