

40 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-081-00063-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Petroleum Co.

Complete Address: Box 1098 Liberal, Kansas

Lease Name Kells B Well No. 1

Location C NW NW Sec. 5 Twp. 28S Rge. (E) 34(W)

County Haskell Total Depth 5710

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Braden Drilling Ind.

Address: 1206 Un. Natl. Bg. Wichita, Kansas License No.

Operation Completed: Hour 11 AM Day 8 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 1881' circulate w/cem.

Heavy mud 5710' to 2800' 70 sax. cem. 2800' to 2575' Heavy mud 2575' to 1900'

10 sax. cem. 1900' to 1875' Heavy mud 1875' to 600' 20 sax. cem. 600' to 540'

Heavy mud 540' to 20' 10 sax. cem. 20' to surface.

Halliburton Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1962 7-10-1962

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 7/10/62

INV. NO. 5348-W

Signed: [Signature]
Well Plugging Supervisor