

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-081-10050-0001

STATE CORPORATION COMMISSION
JUL 19 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

7-19-1965

Operator's Full Name Malonee-Coppenger Operations Inc.

Complete Address: 1207 Union Natl. Bldg. Wichita, Kansas

Lease Name Eubank Well No. # 1

Location C SE SE Sec. 7 Twp. 28 Rge. 34 (E) (W)

County Haskell Total Depth 5403'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberall, Kansas License No. 511

Operation Completed: Hour 10 AM Day 15 Month 7 Year 65

The Above well was plugged as follows:

8 5/8"-1909' Circulated w/cement. 4 1/2"-5722' Cemented. Perforations-5398 1/2'

Plug bottom w/20 Sax. cement top cement 5220'. Mud 5220' to 700'

Spotted 35 Sax. cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 Sax. cement 45' to 0 Pulled 3502' 4 1/2" pipe.

Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/20/65
INV. NO. 1483-W