

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-187-00078-0060 RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

DEC - 8 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kansas Natural Gas Inc.

Complete Address: Box 537 Garden City, Kansas

Lease Name Speck Well No. # 1

Location NW SE Sec. 32 Twp. 28 Rge. 40 (E) (W)

County Stanton Total Depth 2499'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sun Cementing Co.

Address: Liberal, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3 PM Day 6 Month 12 Year 65

The Above well was plugged as follows:

10 3/4" - 482' Circulated w/cement. 7" - 2499' Cemented. Top Perforations - 2244'.

Plug bottom w/20 Sax, cement top cement 2000'. Mud 2000' to 700'.

Spotted 50 Sax. cement 700' to 550'. Mud 550' to 150'.

Plug, 30 Sax. cement 150' to 0. No pipe pulled.

Sun Cementing Co.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 12/9/65

INV. NO. 2374-W

Signed: [Signature]  
Well Plugging Supervisor