

9

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-081-10113-0000

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934, Oklahoma City, Oklahoma

Lease Name Sprunger "A" Well No. 2

Location C NW SE Sec. 20 Twp. 28 Rge. 34 (W)

County Haskell Total Depth 5550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Gas & Oil Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00Pm Day 30 Month 10 Year 1973

The above well was plugged as follows:

8 5/8" to 1909' circulated w/ cement. 5 1/2" to 5521' cemented.

Top perforations 5476' Plug bottom w/ 20 sacks cement.

Top of cement 5400' Mud 5400' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2115' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.
DATE 11/2/73

INV. NO. 8092-U

Signed: [Signature]
Well Plugging Supervisor