

Handwritten mark

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corporation 15-081-66617-0600

Complete Address: Box 1828, Oklahoma City, Oklahoma 73101

Lease Name Sprunger "C" Well No. 1

Location C SE SW Sec. 20 Twp. 28 Rge. 34 ~~W~~ (W)

County Haskell Total Depth 5460'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None Save for S.W.D. at later Date.

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 12 Month 2 Year 1969

The Above well was plugged as follows:

8 5/8" to 1903' circulated w/ cement. 5 1/2" to 5445' cemented.

Top perforations 4709' Plug bottom w/ 25 sacks cement.

Top of cement 4500' Mud 4500' to 1850'

Spotted 35 sacks cement 1850' to 1750' Mud 1750' to 0'.

Pulled 2196' of 5 1/2" casing Company Pump

Welded Plate on 8 5/8" casing w/ 2" vent pipe 4' above ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 2/17/69
INV. NO. 9345-W