

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-081-10063-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Graham-Michaelis Drilling Co. Inc.

Complete Address: 211 North Broadway, Wichita, Kansas 67202

Lease Name Eubank "A" Well No. 2-23

Location C SW SW Sec. 23 Twp. 28 Rge. 34 ~~(E)~~ (W)

County Haskell Total Depth 5550'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 23 Month 9 Year 1969

The Above well was plugged as follows:
8 5/8" to 857' circulated w/ cement. 4 1/2" to 4258' cemented.
Top perforations 4175' Plug bottom w/ 15 sacks cement.
Top of cement 4000' Mud 4000' to 850'
Spotted 40 sacks cement 850' to 750' Mud 750' to 45'
Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump
Pulled 1935' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED RECEIVED
STATE CORPORATION COMMISSION

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 9/26/69 SEP 26 1969
INV. NO. 533-4 CONSERVATION DIVISION
Wichita, Kansas