

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1964

4-27-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Graham-Michaelis 15-081-10067-0000

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name Ubank "B" Well No. # 1-23

Location C NW NE Sec. 23 Twp. 28 Rge. (E) (W) 34

County Haskell Total Depth 5606'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5 PM Day 23 Month 4 Year 64

The Above well was plugged as follows:

8 5/8"-783' Circulated w/cement. 4 1/2"-5450' Cemented. Perforations 5213' to 5236'

Plug bottom w/20 Sax. cement top cement 5150'. Mud 5150' to 700'

35 Sax. cement 700' to 600' Mud 600' to 45'

15 Sax. cement 45' to 0 Pulled 1401' 4 1/2" pipe. Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/28/64  
INV. NO. 9041-W