

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1964  
10-10-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Inc. 15-081-10183-0000

Complete Address: Box 1255 Liberal, Kansas

Lease Name Lightcap Well No. # 11

Location C SE SE Sec. 29 Twp. 28S Rge. 34 (E) (W)

County Haskell Total Depth 5576'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 9 PM Day 7 Month 12 Year 64

The Above well was plugged as follows:

8 5/8"-1863' Circulated w/cement. 4 1/2"-5615' Cemented. Top perforations, 5442'

Plug bottom w/20 Sax.cement top cement 5300'. Mud 5300' to 2400'

Spotted 20 Sax.cement 2400' to 2300'. Mud 2300' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, 15 Sax.cement 45' to 0. Company Pump. Pulled 26 1/4' 4 1/2" pipe.

Cut surface off 5' below ground level and weld on plate.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/10/64

INV.NO. 316-W

Signed: [Signature]  
Well Plugging Supervisor