

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 03 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 069 - 80,006 - 000 (of this well)

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas 67202

Lease Name Nelson Well No. 1

Location NW corner Sec. 17 Twp. 28 Rge. (E) (W) 30

County Gray Total Depth ^{3150'}~~3466'~~

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4 P Day 1 Month 2 Year 1978

The above well was plugged as follows:

Total Depth ^{3150'}~~3466'~~ .8 5/8 csg set 659' cwc 350 sk.

4 1/2 csg set 3142' cw 200 sk cem.

4 1/2 csg PBD 2865' with top perf. (2673'-2679')

Halliburton Cementing Co. pumped down 4 1/2 csg with 100 lbs hulls & 15 sk' cem.

Top of cement 2650' Cutoff & recovered 2474' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water -

followed with 80 sk 50-50 poz 2% -displaced with 10 sk gel & water & capped

with 20 sk 50-50 poz 2% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-3-78

INV. NO. 6703-W

Signed: Geo Massay
Well Plugging Supervisor