

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-3  
Rev. 6-4-68

KANSAS

OCT 27 1980

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

Authority Sept 15, 1980

API Number 15 - 081 - 28194 - 0000 (of this well)

Operator's Full Name Amoco Production Company  
Complete Address P.O. Box 432, Liberal Kansas  
Lease Name J. Watson G.U. Well No. 1  
Location C. W. Sec. 3 Twp 28 Rge. 32(E) (WY)  
County Hashell Total Depth 2970  
Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A       
Other well as hereafter indicated     

Plugging Contractor Dowell Cementing  
Address Wlyses Kansas License No.       
Operation Completed: Hour 4:00 PM Day 23 Month Oct Year 1980

The above well was plugged as follows:

There was 620' of 8 1/8" surface casing C.C.  
5 1/2" set to 2967' perforations 2898-2854'  
1st plug on bottom with 50 lbs cement.  
filled with mud to 800'. 2nd plug at 800'  
with 35 lbs cement. filled with mud  
to 50'. 3rd plug at 50-0 with 10 lbs cement.  
Accomplished by Dowell Cementing.  
No casing salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-29-80  
INV. NO. 4064W

Signed: Richard Thomas  
Well Plugging Supervisor