

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO: J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

~~XXXXXXXX~~ 15-081-00188-0000 Location: SE SE NW

County: Haskell Sec. 18 Twp. 28 Rge. 32W (E) (W)

Name of Field or Pool: _____ Total Depth: 2755'

I have this date completed supervision of plugging of:

Well No. 1 Lease Meairs

Operator's Full Name National Associated Petroleum Co.

Complete Address: Fifth Floor Ritz Bldg. Tulsa, Oklahoma

Plugging Contractor: Patrick Well Service

Address: 1203 N. Calhoun License No. _____

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour _____ Day 28 Month August Year 1960

The above well was plugged as follows:

Halliburton packer set @ 2652.

Spotted 30 sacks of cement on bottom. cement from 2755' back to 2652'

Pulled ten joints of tubing & spotted heavy mud. Mud from 2652' to 2350'

Pulled fifty-four joints of tubing & spotted heavy mud. Mud from 2350' to 668'

Spotted 20 sacks of cement on bridge. Cement from 668' to 500'.

Pulled remaining tubing & mixed heavy mud. Mud from 500' to 10.

Set bridge @ 10' cemented to surface. Cement from 10' to surface.

Remarks: The Halliburton packer was left in the hole @ 2652'
I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: [Signature]
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

[Signature]
signed for Frank Broadfoot
6-19-62

Signed: _____
Well Plugging Supervisor

Reviewed: _____
Field Supervisor

Remarks:

INVOICED

DATE 6/19/62

INV. NO. 5200-W