

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

ORIGINAL

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15 - 155 - 21287-000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BASYE WELL SERVICING COMPANY OPERATORS LICENSE NO. 05670

ADDRESS P. O. Box 149  
Stafford, Kansas 67578 PHONE # (316) 234-5235

LEASE (FARM) Joy Royse #2 WELL NO. 2 WELL LOCATION C NE NE NE COUNTY Reno

SEC. 20 TWP. 25S RGE. 9W ~~(R) or (W)~~ TOTAL DEPTH 3965' PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 181 KB CEMENTED WITH 200 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Heavy mud to 1350' with 35 sacks;

heavy mud to 950' with 35 sacks; heavy mud to 240' with 35 sacks; heavy mud to 60'

with 25 sacks to surface; 15 sacks in rathole. Use 60/40 Pozmix with 4% gel  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 PM, 9-7-93.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Vaughn Thompson PHONE # (316) 278-2131

ADDRESS Sterling, Kansas 67579-0129

PLUGGING CONTRACTOR STERLING DRILLING COMPANY LICENSE NO. 5142

ADDRESS P. O. Box 129  
Sterling, Kansas 67579-0129 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Richard L. Mead  
(Operator or Agent)

Richard L. Mead, Vice President

DATE: September 8, 1993

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG ----- JOY ROYSE #2

Located: C NE NE NE, Section 20-25S-9W, Reno  
County, Kansas

OWNER: Bayse Well Servicing Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 3, 1993

COMPLETED: September 8, 1993

TOTAL DEPTH: 3965

## LOG

0 - 55 Surface Soil and Sand  
55 - 185 Red Bed  
185 - 499 Red Bed and Shale  
499 - 1050 Shale  
1050 - 3965 Lime and Shale

## CASING RECORD

Spudded at 7:15 AM, 9-3-93. Drilled  
185' of 12 1/4" hole. Ran 4 joints  
8 5/8", 23# casing. 169.67' pipe  
set at 181' K.B. Cemented with 200  
sacks 60/40 Pozmix with 2% gel and  
3% cc. Plug down at 10:45 AM, 9-3-93,  
by Allied Cementing Company.  
  
Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1993

CONSERVATION DIVISION  
Wichita, Kansas

Deviation Surveys:

1/4° at 185'  
1 1/4° at 3965'