

STATE OF KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

15-187-00328-0000

API # NA (SPUD 12/17/52) (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 (owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE PLUMMER WELL# 1-10 SEC. 10 T. 28S R. 40 (XXXX/West)

NE - NE - NE - SW SPOT LOCATION/QQQQ COUNTY STANTON

2540 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

2540 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 10" SET AT 300' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 7" SET AT 2194' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: OPEN HOLE 2194-2401'

ELEVATION 3250' / -- T.D. 2401' PBD 2401' ANHYDRITE DEPTH NA (G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH W/2-3/8" TBG. CIRC. HOLE W/9 PPG MUD. SPOT 20 SKS CMT FROM 2194'-2144'. TOH W/2-3/8" TBG. PULL ON 7" CSG AND SPOT 30 SKS CMT @ CUTOFF POINT. TOH W/7" CSG. SPOT 35 SKS FROM 350-250'. TOH W/7" CSG AND SPOT 20 SKS CMT FROM 53-3'. CUT OFF 10" SURFACE CSG 3' BELOW GL AND CAP. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31154

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/1/97 AUTHORIZED OPERATOR/AGENT: JOHN A. BROMAN (Signature) DIV. PROD. ENG.

RECEIVED stamp: KANSAS RECEIVED COMMISSION 8-4-97

8-4-97

ANADARKO PETROLEUM CORPORATION

PHONE 316 - 624 - 6253 1701 NORTH KANSAS AVE. P.O. BOX 351 LIBERAL, KANSAS 67905 - 0351



15-187-00398-0000

August 1, 1997

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202

Attn: Mr. Jeff Klock

Re: Well Plugging Application Form (Form CP-1)

Plummer 1-10
Sec. 10-28S-40W
Stanton County, Kansas

Stevens 1-13
Sec. 13-30S-35W
Grant County, Kansas

Dear Jeff:

Enclosed in duplicate is a well plugging application (Form CP-1) for each of the referenced wells. The Plummer 1-10 is being resubmitted due to delay in completion & testing of replacement well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

John A. Broman
Division Production Engineer
AMC/sjc

Enclosures

cc: Well File
L. M. Harvey
Sargent & Horton Plugging, Inc.
TRC - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.doc

RECEIVED
KANSAS CORP COMM
1997 AUG -11 A 2:03



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

15-187-00328-0000

August 5, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Plummer #1-10
API 15-N/A
2540 FSL 2540 FEL
Sec. 10-28S-40W
Stanton County

Dear Mr. Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760