

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

BLM-TULSA

KS NM 68736

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

OCT 19 11 23

KS NM 74120X

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other Injection well

2. Name of Operator

Anadarko Petroleum Corporation

3. Address and Telephone No.

P. O. Box 351, Liberal, Kansas 67905-0351 (316) 624-6253

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NE SW SW 660' FSL & 660' FWL Section 16-34S-43W
(Formerly Panhandle Eastern, Interstate "C" No. 02

7. If Unit or CA, Agreement Designation

14-08-0001-8657

8. Well Name and No.

Interstate Unit No. 24*

9. API Well No.

15-129-10494-00-01

10. Field and Pool, or Exploratory Area

Interstate Purdy Morrow

11. County or Parish, State

Morton County, Kansas

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☒ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Subsequent Report to Plug and Abandon a temporarily abandoned injection well.

Original Completion Date: 8-3-56

Date of Unitization: 4-1-65

Converted to Injection: 11-24-82

Date Plugging Completed: 9-19-94

Plug and Abandon Procedure: MIRU csg pullers. Ran 1-1/4" tbg to 4120'. Circ hole w/mud. Spot 10 sxs cmt plg from 4120-4020'. Ld 1-1/4" tbg. Shot csg off @ 2318'. Csg would not pull. Shot off csg @1628', spot 50 sxs cmt plg from 1250-1100', 40 sxs cmt plg from 650-550', 10 sxs cmt plg from 33-3'. Cut off 7" csg 3' below gl and cap. Rec'd 54 lbs 4-1/2" csg. State Witness: Glenn Barlow. Restore location and contact USFS.

14. I hereby certify that the foregoing is true and correct

Signed

Title Division Production Manager

Date 10-11-94

(This space for Federal or State office use)

Approved by (ORIG. SGD.) VIRGIL L. PAULI

Title CHIEF, BRANCH OF FLUID OPERATIONS

Date

OCT 24 1994

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Kansas Corporation Commission

*See Instruction on Reverse Side