

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

BLM-710 USA D.C.

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.  
KS NM 69306

6. If Indian, Allottee or Tribe Name

**SUBMIT IN TRIPLICATE**

1. Type of Well  
 Oil Well  Gas Well  Other Injector

2. Name of Operator  
Anadarko Petroleum Corporation

3. Address and Telephone No.  
P. O. Box 351, Liberal, Kansas 67905-0351 (316) 624-6253

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
SE NE Section 29-34S-43W

\*Formerly Musgrove Petroleum Corp. Roll No. 4

7. If Unit or CA. Agreement Designation  
(KS NM 74120X)  
14-08-0001-8657

8. Well Name and No.  
Interstate Unit No. 59\*

9. API Well No.  
15-129-10445-00-00  
11-21-56 Drill Date

10. Field and Pool, or Exploratory Area  
Interstate Purdy Morrow

11. County or Parish, State  
Morton, Kansas

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input checked="" type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Notice of Intention to Plug & Abandon a temporarily abandon injector that has no further utility to the Unit.

Original Completion Date: 11-28-56  
Date of Unitization: 4-1-65  
Converted to Injection: 1-18-83  
Anticipated Plugging Date: Upon KCC Approval  
Proposed Plugging Method: TIH w/1 1/4" workstring & circ hole w/9 ppg mud. Spot 20 sxs cmt from 4200-4100' (tbg displacement - 4.5 bbls). TOH w/1 1/4" workstring. Pull free point & cut off 5 1/2" csg. Spot 30 sxs cmt at cut off depth. Spot 70 sxs cmt @ 1232-1032'. Spot 40 sxs cmt @ 650-550'. Spot 20 sxs cmt @ 50-3'. Cut off 8 5/8" csg 3' below ground level & cap. Restore location.

BIA \_\_\_\_\_  
OTHER AGENCY Kansas Corporation Commission  
TECH \_\_\_\_\_  
LEASE FILE \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1993

14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title Division Production Manager

CONSERVATION DIVISION  
Date 2/24/93

(This space for Federal or State office use)  
APPROVED: (SIGNED) VIRGIL L. PAULI

Title CHIEF, BRANCH OF FLUID OPERATIONS

Date FEB 24 1993

Approved by \_\_\_\_\_  
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.