

1-26-87

1  
060931

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-057-20,139-0000

N/2 SW NW SEC. 11, T 28 S, R 21 (W/E)

3630 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Hicks "A" Well # 1

Operator: Pickrell Drilling Company, Inc.  
Name & Address 110 North Market, Suite 205  
Wichita, KS 67202

County Ford 165.20

Well Total Depth 5083 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 606

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 26 Month: 1 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 5083' PBT 5024' Perfs at 5015-19'

1st plug pump 1 sx hulls and 1 sx hulls mixed with 25 sx cement. Stop plug at 4666'.

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 26 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 1 sx hulls mixed with 25 sx cement. Stopped plug at 4666'.

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION  
JAN 28 1987

Maximum pressure 600 psi and shut in 400 psi. Recovered 3500' of 4 1/2" casing

Remarks: Used 60/40 Pozmix 6% gel by Allied. Richard Lacey saw bottom plug. 1-28-87  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 1-29-87

INV. NO. 16018