

1 050761

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,193-0660

NE NE, SEC. 2, T 28 S, R 21 W EX

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Birney Estate Well # "B" 1

Operator: Pickrell Drilling Company

County Ford 164.45

Name & Address 110 N. Market, Suite 205

Well Total Depth 5060 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 620

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 5:30 pm Day: 6 Month: February Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 5059' Perfs at 4964-4976'

1st plug sand back to 4900' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 160 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 6 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 160 sx cement.

Cemented two water wells.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 3500' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION Signed

Richard W. Lacey (TECHNICIAN)

DATE FEB 11 1986

FEB 10 1986

INV. NO. 12545

CONSERVATION DIVISION Wichita Kansas

FORM CP-2/3 Rev. 01-84