

1 060401

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,346-6000  
150' W  
SW NW, SEC. 1, T 28 S, R 21 W/E  
3450 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123  
Operator: Pickrell Drilling Company  
Name:  
Address 110 North Market, Suite 205  
Wichita, KS 67202

Lease Name Harsha "C" Well # 1  
County Ford 165.75  
Well Total Depth 5100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 583

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 26 Month: October Year: 19 84

Plugging proposal received from Byron Clawson  
(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" set at 5090' PBD 5052 Perfs at 4985-94'  
1st plug sand back to 4935' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 12:00 noon Day: 27 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5090' PBD 5052' Perfs at 4985-94'  
1st plug sanded back to 4935' and dumped 4 sx cement on top of sand through bailer,  
2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,  
released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
11-20-84  
NOV 20 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 4100' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 12-4-84  
INV. NO. 5770

Signed Paul A. Luthi  
(TECHNICIAN)

15-057-20346-0000

— 583' Base 8 5/8" w/ 300 Sx

HARSHA C-1

— 4400 ESTIMATED T.O.C.

≡ ≡ ≡ 4985-4994 (Miss Perfs)

— 5052 PBTD (Loggers)

— 5090' Base 4 1/2" 10.5# KS Csq w/ 150 Sx

— 5100' RTD

RECEIVED  
STATE CORPORATION COMMISSION

SEP 06 1991

CONSERVATION DIVISION  
Wichita, Kansas