

1 040973

6-7

API NUMBER 15- 097-21,285-00-00

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

W/2. SE SE, SEC. 27, T 28 S, R 20 W/E
660 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Sloan Well # 2

Operator: J. Mark Richardson

County Kiowa 164.81

Name: J. Mark Richardson
Address 155 N. Market, Ste. 840

Well Total Depth 5071 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 610

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 31201

Address: 303 E. Kansas, Greensburg, KS

Company to plug at: Hour: 9:30 a.m. Day: 7 Month: 6 Year: 19 95

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

Work: 4 1/2" at 5070' w/300 sx cement, PBTD 4720', Perfs at 4662-68'

1st plug sand 4 1/2" casing back to 4610' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 7 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4610' and dumped 4 sx cement on top of sand bridge through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 350 psi.

6-15-95

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3274' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-26-95
INV. NO. 42996

Signed *Stephan J. Dejeu* (TECHNICIAN)

RECEIVED THE CORPORATION COMMISSION JUN 15 1995