

To: 1 051689 7-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,646A-00-0
C NW NW , SEC. 22 , T. 28 S, R. 20 W/EX
4660 feet from S section line
4620 feet from E section line
Lease Name Price T Well # 1 OWWO
County Kiowa
Well Total Depth 5184. 168.48 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 325

TECHNICIAN'S PLUGGING REPORT
Operator License # 4243
Operator: CROSSBAR PETROLEUM INC.
Name & Address 220 W. DOUGLAS, STE. 140
WICHITA KS 67202

Abandoned Oil Well Gas Well Input Well SHD Well D&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS

Company to plug at: Hour: 10 a.m. Day: 7 Month: 7 Year: 1993

Plugging proposal received from Tom Larson
(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 5184' w/175 sx cement, CIBP 4360', Perfs at 4923-49, 4334-44'
1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150. sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11:05 a.m. Day: 7 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

7-9-93

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2920' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.) JUL 9 1993

INVOICED
DATE JUL 19 1993
INV. NO. 38138

observe this plugging.
Signed Richard W. Lacy
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas