

1 051690 7-7  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,297-0000  
200' N of  
NW SW, SEC. 22, T. 28 S, R. 20 N/E

2180 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4243  
Operator: CROSSBAR PETROLEUM INC.  
Name & Address: 220 W. DOUGLAS, STE 140  
WICHITA KS 67202

Lease Name Aldrich Well # 1  
County Kiowa  
Well Total Depth 5600 182.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS

Company to plug at: Hour: 11:45 a.m. Day: 7 Month: 7 Year: 1993

Plugging proposal received from Tom Larson  
(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 5565' w/150 sx cement, Perfs at 5314-18, 4923-26', 4584-86', 4327-37', CIBP @5280'  
1st plug set CIBP at 4250' with 2 sx cement on top,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12:55 p.m. Day: 7 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4250' with 2 sx cement on top,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.  
Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3652' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form)

INVOICED

DATE JUL 19 1993  
INV. NO. 38139

Signed Richard W. Lyon (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
7-9-93  
HUB - 9 1995