

1041125

API NUMBER 15-151-21,762 - 00-00

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION

130 S. Market, Room 2078

Wichita, KS 67202

11-22

E/2 NE SE, SEC. 24, T 28 S, R 15 W/4

1980 feet from S section line

330 feet from E section line

Lease Name Cowen Well # 1

County Pratt

Well Total Depth 4716 153.27 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 336

TECHNICIAN'S PLUGGING REPORT

Operator License # 31288

Operator: Southwind Consulting

Name: P.O. Box 912

Address: Pratt, KS 67124

Pratt, KS 67124

Abandoned Oil Well X Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 11 Year: 19 95

Plugging proposal received from Lee Brown

(company name) Southwind Consulting (phone) 316-672-9284

logs: 4 1/2" at 4712' w/175 sx cement, Perfs at 4541.5-4549.5, 4543-47, 4576-80'

1st plug sand back to 4490' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 a.m. Day: 22 Month: 11 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4490' and dumped 4 sx cement on top of sand

bridge through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement

Maximum pressure 1850 psi and shut in 250 psi.

RECEIVED STATE CORPORATION COMMISSION DEC 4 1995 12-04-95 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2360' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-95

INV. NO. 44183

11-22

Signed Stephen J. Pfeifer (TECHNICIAN)