

1030277

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,124-00-00
C SW SW NE, SEC. 22, T 28 S, R 15 W/X
2970 feet from N SE Corner of ~~XXX~~ section line
2310 feet from W SE Corner of ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7105
Operator: Spines Exploration, Inc.
Name & Address 530 Fourth Financial Center
Wichita, KS 67202

Lease Name Winklepleck Well # 1
County Pratt
Well Total Depth 4850 157.63 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 421

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:00 pm Day: 20 Month: September Year: 19 84

Plugging proposal received from Ken Gates

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" set at 4790' Perfs 4642-4300' PBD 4790'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 125 sx cement

Plugging Proposal Received by Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:55 pm Day: 20 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4790' Perfs 4642-4300' PBD 4790'

1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 500 psi and shut in pressure 300 psi

RECEIVED
STATE CORPORATION COMMISSION
9-2484
SEP 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If ~~XXX~~ observe this plugging.)

Signed Steve Shumant
(TECHNICIAN)

DATE 10-2-84

INV. NO. 3985

9-20