

To: 1 050721
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,486 - 00-00

NW NW SE , SEC. 22 , T 28 S, R 15 (W/R)
2310 feet from (S) section line
2310 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Frazier Well # 1

Operator: Brougner Oil, Inc.
Name & Address: Drawer 1367
Great Bend, KS 67530

County Pratt
Well Total Depth 4857 157.85 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 10 Month: December Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4849' Perfs at 4574-4580 Well has been squeezed - hole in the pipe.

1st plug pump 1 sack hulls and 50 sx common cement and stop plug at 2093'

pump 1 barrel sand and 5 sx cement through bailer
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:40 am Day: 10 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 50 sx common cement to bottom

and stopped plug at 2093', Well had been squeezed. Hole in the pipe. 2nd plug 1 barrel

of sand and 5 sx cement through bailer, 3rd plug squeezed well with 3 sx hulls, 10 sx gel,

50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx

cement.

Maximum pressure 550 psi and shut in 400 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1900' 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

I (xxx / did not) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

DEC 20 1985

12-20-85

DATE DEC 20 1985

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84