

9-20

R

1 061137

API NUMBER 15- 151-21,543 - 00.00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 SW NE, SEC. 22, T 28 S, R 15 W/EX
2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Winklepeck Well # 1

Operator: Pintail Properties
Name & Address 412 East Douglas, Suite 1
Wichita, KS 67202

County Pratt 157.37

Well Total Depth 4842 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 20 Month: 9 Year: 19 88

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4840' Perfs at 4309-12'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1988

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Hour: 10:30 a.m. Day: 20 Month: 9 Year: 19 88

CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3468' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 10-6-88

INV. NO. 22532