

1 20846

10-15

15-151-00325-00-0;

API NUMBER 15-Docket #D-19,770

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE, SEC. 6, T 29 S, R 11 W,
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6588

Lease Name Blackwelder Well / 1

Operator: Woodman-Iannitti Oil Co.

County Pratt

Name: P.O. Box 308

Well Total Depth 4321 feet

Address: Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Oil Co. License Number 6588

Address: P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 15 Month: 10 Year: 19 93

Plugging proposal received from Dick Iannitti

(company name) Woodman-Iannitti Oil Co. (phone) 316-792-2921

were: 2-7/8" casing at 3808', Top of cement @ 2600', Perfs at 3286-3306', PBTD 3784'

1st plug fill 2 7/8" casing with cement.

2nd plug pump 150 sx cement in 2 7/8" X 8 5/8" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 15 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug filled 2 7/8" casing with 100 lbs. hulls and 75 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi.

2nd plug pumped in annulus with 300 lbs. hulls and 150 sx cement. Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. (if additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 10-20-93 OCT 20 1993

I (did / ~~XXXXXX~~) observe this plugging.

Signed _____ (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas