

1 090012

8-4

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,550-00-00

NW NW, SEC. 4, T 29 S, R 11 W/R

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Weir "A" Well # 1

Operator: Kansas Petroleum, Inc.

County Pratt 86.61

Name & Address 225 North Market, Suite 310

Well Total Depth 2665 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 9 a.m. Day: 4 Month: 8 Year: 19 89

Plugging proposal received from James Tasheff

(company name) Kansas Petroleum Inc. (phone) 316-267-2266

were: 4 1/2" at 2664' PBD 2660' Perfs at 2651-57'

1st plug set CIBP at 2630' with 2 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10 a.m. Day: 4 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2610' and pumped 2 sx cement,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 450 psi.

RECEIVED STATE CORPORATION COMMISSION

AUG 9 1989

08-09-89

CONSERVATION DIVISION of Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1600' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(old) observe this plugging.

DATE 8-15-89

Signed Michael R Wilson (TECHNICIAN)

INV. NO. 25606