

1 120291

API NUMBER 15- 151-20,984 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2 E/2 SE, SEC. 6, T 29 S, R 12 W/K
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1320 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Riffey Well # 2

Operator: Hummon Corporation
Name:
Address 400 One Main Place
Wichita, KS 67202

County Pratt 147.71

Well Total Depth 4545 feet

Conductor Pipe: Size 10 3/4 feet 231

Surface Casing: Size 8 5/8 feet 800

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 24 Month: 8 Year: 19 89

Plugging proposal received from Judy

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4541' PBSD 4480' Perfs at 4448-50' Elevation 1900' KB

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p. Day: 24 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4400' and dumped 4 sx cement,
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1989

Pumping: pressure 0-250 psi and shut in 130 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3268' of casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-6-89 observe this plugging.

Signed Duan Rankin
(TECHNICIAN)

DATE 9-6-89
INV. NO. 25792