

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21304-00-00
Spot: CSWSE Sec/Twnshp/Rge: 4-29S-12W
660 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: NEEL Well Number: 3
County: PRATT Total Vertical Depth: 4334 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

Conductor Pipe: Size feet: \$140.86
Surface Casing: Size 8.625 feet: 387 WITH 350 SX CMT
Production: Size 5.5 feet: 4325 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/29/2002 8:50 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4170' & 5 SX CMT. 1ST PLUG AT 770' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 410' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/29/2002 10:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4306.98'. PERFS AT 4278-82, BOLT PLUG @ 4275'. PERFS AT 4268-72, CIBP @ 4250'. PERFS AT 4226-28'. SAND TO 4170' & 5 SX CMT. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 770'. 2ND PLUG PULL TO 410' & SPOT 50 SX CMT. 3RD PLUG SPOT 10 SX CMT AT 0-40'. GOOD CIRCULATION.


RECEIVED
MAY 31 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2830' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

INVOICED

DATE

5-31-02

MAY 30 2002

INV. NO.

2002061875-MP

